

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 56

APPROVED TENDER SCHEDULE -'B'

No EEY/NK-D/E-PMT/05/2012-13 Dated: 13-12-2013

Item No: 45

Name of Work: -Improvements to drain at 407 2nd A main near Ayurvedic Clinic in in Attur, ward no:03.....

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY	
				Rate	Rate in Words
1	KSRRB 300-1:Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 Meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specifications and complete as per specifications with all load and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	149.34	55.00	Rupees fifty five only
2	Removing B.S Slab of Drain and stacking	Sqm	421.20	45.00	Rupees forty five only
3	Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	421.20	65.00	Rupees sixty five only
4	Providing 7.5 cm thick granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.	Sqm	105.30	280.00	Rupees two hundred eighty only
5	KSRRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement at 180kgs. with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications. Specification with all lead and lift complete as per specification as per direction of Engineer incharges	Cum	13.65	3800.00	Rupees three thousand eight hundred only
6	KSRRB 5-1.4:Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry(guoin, jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to IS:2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	156.00	850.00	Rupees eight hundred fifty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY	
				Rate	Rate in Words
7	KSRB 5-1.5: Providing and constructing non-load bearing wall with cement concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (jamb, closer blocks) with blocks of size 40x10x20 (lxbxh) cms conforming to IS:2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	Sqm	155.00	520.00	Rupees five hundred twenty only
8	KSRB-4-1.6 : Providing and laying in position plain cement concrete of mix M 15 with OPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications. Specification	Cum	11.70	4430.00	Rupees four thousand four hundred thirty only
9	Providing and fixing 10 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick well compacted cost of all materials labour curing complete as per specification (Data Rate Approved)	Sqm	35.00	1498.00	Rupees one thousand four hundred ninety eight only
10	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/anker/moorum. KSRRB M100-1: Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1	Cum	143.34	70.00	Rupees seventy only

Signature of the Contractor

Executive Engineer,
Yelabanka Division,
B&M.P., Bengaluru-64.